

SPE-0109

~~SES-110~~

SE-85-6-7
SL-100-490(K)
SL-100-SPE

Ottawa, September 11, 1967.

Sangamo Company Limited,
215 Laird Drive,
LEASHE, (Toronto 17),
Ontario.

Attention: Mr. M. R. Selvidon, P.Eng.,
Engineering Department.

Cancelled & replaced by SPE-110 of Sept 19. 1967 see above

SPECIAL APPROVAL - One Only - Sangamo Type "SC2" Graphic Thermal Demand Meter with 20% Raised Zero, Serial Number 6914229

Dear Sirs:

This is to advise that Special Approval has been granted by the Standards Branch for use in Canada for billing purposes to the above-named apparatus.

This instrument is rated at 120 volts, 5 amps., 60 Hz., 3-phase, 3-wire, 2-element, 0.2-0.0.3 Kv full scale, testing time 32 min.

The installation will be at Lakehead University, Port Arthur, Ontario on a 23 kv 3-phase 3-wire service and is used with a Ferranti Packard type "RT-25" metering unit with two 23000/115 volt potential transformers and two 300/150-5 amp. current transformers; it is expected that it will be used to measure RVA.

Yours very truly,

W. J. G. Fraser
(for) W. J. G. Fraser, Chief,
Electricity and Gas Division,
Standards Branch.

EAW/nee

c.c. to: Mr. J. F. Priggs, Dist. Insp. of Electricity and Gas, Fort William
c.c. to: Lakehead University (through Mr. Priggs)